

PRODUCTION

All the insert and conductive parts of the CT Terminals are manufactured with best quality material experienced in Turkey by TAKFAN.

TESTING

The terminal block shall be air pressure leak tested at 1 bar for 15 minutes, where there should be no signs of air leakage.

6 WAY CT TERMINAL

TK CT-6





